

## SECTION 015000

### MOBILIZATION

#### PART 1 - GENERAL

##### 1.1 DEFINITION AND SCOPE

A. As required for the proper performance and completion of the Work, mobilization shall include, but not be limited to, the following principal items:

1. Move onto the Site all Contractor's equipment required for the first month's operation.
2. Install silt fences around perimeter of Project Site and at locations where surface drainage discharges to existing stormwater inlets.
3. Install temporary construction power, wiring, and lighting facilities.
4. Establish a fire protection plan and safety program.
5. Secure construction water supply.
6. Provide on-site sanitary facilities and potable water facilities.
7. Arrange for and erect Contractor's work and storage yard and employee's parking facilities.
8. Submit all required insurance certificates and bonds in accordance with the Front End Documents.
9. Obtain all required permits.
10. Post all OSHA, FDEP, Department of Labor, and all other required notices.
11. Have Contractor's project manager and/or superintendent at the job site full time.
12. Submit a detailed progress schedule acceptable to the City and approved for baseline schedule.
13. Submit a finalized Schedule of Values of the Work in the City's approved format as provided in Section 012973 - Schedule of Values.

14. Submit a hurricane preparedness plan acceptable to the City.
15. Submit signed and sealed Maintenance of Traffic and Control Plan to the City.
16. Erect all required Project signs.
17. Submit Contractor's Health and Safety Plan.
18. Submit Contractor's Quality Control Plan.

1.2 PAYMENT FOR MOBILIZATION

- A. The Contractor's attention is directed to the condition that no payment for mobilization, or any part thereof, will be approved for payment under the Agreement until all mobilization items listed above have been completed as specified.
- B. Measurement and Payment for Mobilization shall be made per Section 012000 – Measurement and Payment.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION (NOT USED)

END OF SECTION